

§ 1. 工事数量総括表

大坪地域北工業団地造成その3工事

工事区分(レベル1)		規格	単位	数 量		摘要
工種(レベル2)				計算値	設計値	
種別(レベル3)						
細別(レベル4)						
土工						
土工						
掘削工						
切土		A + G + B + H 0.00 + 101.62 + 93.70 + 445.27	m3	640.6	640	
掘削		(盛土 + 路床盛土 - 切土) - (スマートIC + 白萩南部) (12,277.56 + 1,696.75 - 640.59) - (4,200.00 + 9,000.00)	m3	133.7	130	公共残土仮置場より
盛土		A + G + B + H - (仮設道路盛土 + 側溝分) 7,135.90 + 3.35 + 5,289.88 + 0.00 - (140.35 + 11.22)	m3	12,277.6	12,300	
道路工						
路床盛土		E + F - 仮設道路盛土 1,325.40 + 795.90 - 424.55	m3	1,696.8	1,700	
仮設工						
工事用道路工						
敷鉄板設置撤去		(1.524 × 6.096)m2 × 102枚	m2	947.6	948	
敷鉄板賃料			枚	102	102	
仮水路工						
掘削		(1.58 + 0.50) × 0.30 ÷ 2 × 116.3	m	36.3	36	
築堤盛土		(1.58 + 0.50) × 0.30 ÷ 2 × 116.3	m	36.3	36	
共通仮設費						
仮設材運搬費						
仮設材等運搬費		1.604t/枚 × 102枚	t	163.61	163.6	

土量計算書

街区	面積 (m2)	計画高 (m)	路盤下高 (m)	現況高 (m)	表土剥ぎ後 地盤高(m)	高低差 (m)	盛土 (m3)	切土 (m3)	表土厚 (cm)	表土剥ぎ 土量(m3)	場内運搬 距離(m)	土量×距離	備考
A-1	344.2	27.25	27.25	26.26	26.06	1.19	409.60		20.00	68.84	92.00	6333.28	
A-2	447.3	27.35	27.35	26.87	26.70	0.65	290.75		17.00	76.04	105.00	7984.20	
A-3	109.4	27.54	27.54	27.03	26.83	0.71	77.67		20.00	21.88	108.00	2363.04	
A-4	44.6	27.64	27.64	27.25	27.05	0.59	26.31		20.00	8.92	107.00	954.44	
A-5	183.1	27.27	27.27	26.62	26.52	0.75	137.33		10.00	18.31	87.00	1592.97	
A-6	257.4	27.32	27.32	26.71	26.61	0.71	182.75		10.00	25.74	82.00	2110.68	
A-7	326.6	27.50	27.50	26.87	26.70	0.80	261.28		17.00	55.52	95.00	5274.40	
A-8	405.3	27.55	27.55	27.03	26.84	0.71	287.76		19.00	77.01	81.00	6237.81	
A-9	90.5	27.43	27.43	26.85	26.72	0.71	64.25		13.00	11.77	79.00	929.83	
A-10	184.3	27.20	27.20	26.20	26.03	1.17	215.63		17.00	31.33	58.00	1817.14	
A-11	478.6	27.21	27.21	26.48	26.30	0.91	435.53		18.00	86.15	63.00	5427.45	
A-12	1,359.9	27.29	27.29	26.71	26.57	0.72	979.13		14.00	190.39	54.00	10281.06	
A-13	55.8	27.49	27.49	26.95	26.80	0.69	38.50		15.00	8.37	50.00	418.50	
A-14	596.2	27.62	27.62	27.16	27.00	0.62	369.64		16.00	95.39	56.00	5341.84	
A-15	276.3	27.75	27.75	27.26	27.10	0.65	179.60		16.00	44.21	34.00	1503.14	
A-16	345.2	27.61	27.61	27.17	27.01	0.60	207.12		16.00	55.23	28.00	1546.44	
A-17	1,042.0	27.45	27.45	26.92	26.75	0.70	729.40		17.00	177.14	21.00	3719.94	
A-18	237.6	27.24	27.24	26.64	26.47	0.77	182.95		17.00	40.39	14.00	565.46	
A-19	430.5	27.20	27.20	26.37	26.24	0.96	413.28		13.00	55.97	33.00	1847.01	
A-20	198.1	27.20	27.20	26.43	26.30	0.90	178.29		13.00	25.75	12.00	309.00	
A-21	75.7	27.20	27.20	26.60	26.46	0.74	56.02		14.00	10.60	12.00	127.20	
A-22	331.9	27.64	27.64	27.30		0.34	112.85			0.00			現況：農道
A-23	37.6	27.33	27.33	26.54	26.39	0.94	35.34		15.00	5.64	4.00	22.56	
A-24	61.2	27.38	27.38	26.31	26.17	1.21	74.05		14.00	8.57	12.00	102.84	
A-25	205.6	27.48	27.48	26.88	26.73	0.75	154.20		15.00	30.84	8.00	246.72	
A-26	242.4	27.67	27.67	26.85	26.70	0.97	235.13		15.00	36.36	9.00	327.24	
A-27	58.7	27.80	27.80	26.89	26.71	1.09	63.98		18.00	10.57	3.00	31.71	
A-28	112.6	27.60	27.60	26.67	26.52	1.08	121.61		15.00	16.89	6.00	101.34	
A-29	45.8	27.83	27.83	27.28		0.55	25.19			0.00			現況：農道
A-30	239.5	27.97	27.97	27.13	26.98	0.99	237.11		15.00	35.93	10.00	359.30	
A-31	436.6	27.80	27.80	27.19	26.99	0.81	353.65		20.00	87.32	16.00	1397.12	
小計	9,260.5						7135.90	0.00		1417.07		69273.66	(1街区)
				</									

土量計算書

街区	面積 (㎡)	計画高 (m)	路盤下高 (m)	現況高 (m)	表土剥ぎ後 地盤高(m)	高低差 (m)	盛土 (m3)	切土 (m3)	表土厚 (cm)	表土剥ぎ 土量(m3)	場内運搬 距離(m)	土量×距離	備考
B-1	15.6	25.25	25.25	24.88	24.73	0.52	8.11		15.00	2.34	36.00	84.24	
B-2	164.8	25.28	25.28	24.73	24.58	0.70	115.36		15.00	24.72	42.00	1038.24	
B-3	146.0	25.43	25.43	24.90	24.75	0.68	99.28		15.00	21.90	46.00	1007.40	
B-4	528.5	25.62	25.62	25.13	24.96	0.66	348.81		17.00	89.85	52.00	4672.20	
B-5	806.0	25.88	25.88	25.39	25.24	0.64	515.84		15.00	120.90	67.00	8100.30	
B-6	376.2	26.06	26.06	25.56	25.41	0.65	244.53		15.00	56.43	73.00	4119.39	
B-7	480.4	26.16	26.16	25.73	25.57	0.59	283.44		16.00	76.86	74.00	5687.64	
B-8	196.8	26.39	26.39	25.90	25.74	0.65	127.92		16.00	31.49	85.00	2676.65	
B-9	202.3	26.32	26.32	26.26	26.06	0.26		-52.60	20.00	40.46	78.00	3155.88	
B-10	143.4	26.22	26.22	25.92	25.78	0.44	63.10		14.00	20.08	67.00	1345.36	
B-11	109.0	26.16	26.16	26.37	26.24	-0.08		8.72	13.00	14.17	29.00	410.93	
B-12	1,178.0	26.05	26.05	26.03	25.85	0.20	235.60		18.00	212.04	30.00	6361.20	
B-13	1,108.7	25.90	25.90	25.80	25.63	0.27	299.35		17.00	188.48	31.00	5842.88	
B-14	1,249.3	25.63	25.63	25.49	25.35	0.28	349.80		14.00	174.90	24.00	4197.60	
B-15	959.4	25.35	25.35	25.15	25.00	0.35	335.79		15.00	143.91	22.00	3166.02	
B-16	502.8	25.75	25.75	25.94		-0.19		95.53					現況：農道
B-17	19.9	26.25	26.25	26.43	26.30	-0.05		1.00	13.00	2.59	6.00	15.54	
B-18	605.6	26.23	26.23	26.31	26.17	0.06	36.34		14.00	84.78	10.00	847.80	
B-19	1,315.4	26.05	26.05	26.00	25.84	0.21	276.23		16.00	210.46	35.00	7366.10	
B-20	90.8	26.40	26.40	26.06	25.91	0.49	44.49		15.00	13.62	20.00	272.40	
B-21	353.4	26.23	26.23	25.97	25.78	0.45	159.03		19.00	67.15	37.00	2484.55	
B-22	25.1	25.88	25.88	25.66	25.50	0.38	9.54		16.00	4.02	60.00	241.20	
B-23	88.8	25.98	25.98	25.76	25.60	0.38	33.74		16.00	14.21	60.00	852.60	
B-24	113.5	25.94	25.94	26.20		-0.26		29.51					現況：農道
B-25	364.9	25.98	25.98	25.82	25.70	0.28	102.17		12.00	43.79	13.00	569.27	
B-26	819.0	25.80	25.80	25.76	25.58	0.22	180.18		18.00	147.42	21.00	3095.82	
B-27	800.4	25.60	25.60	25.49	25.30	0.30	240.12		19.00	152.08	22.00	3345.76	
B-28	903.8	25.40	25.40	25.25	25.05	0.35	316.33		20.00	180.76	21.00	3795.96	
B-29	282.2	25.23	25.23	24.97	24.79	0.44	124.17		18.00	50.80	28.00	1422.40	
B-30	550.9	25.34	25.34	25.03	24.89	0.45	247.91		14.00	77.13	52.00	4010.76	
B-31	319.8	25.52	25.52	25.23	25.07	0.45	143.91		16.00	51.17	55.00	2814.35	
B-32	215.3	25.63	25.63	25.30	25.15	0.48	103.34		15.00	32.30	51.00	1647.30	
B-33	72.6	25.65	25.65	25.73		-0.08		5.81					現況：農道
B-34	52.1	25.85	25.85	25.96		-0.11		5.73					現況：農道
B-35	465.5	25.76	25.76	25.49	25.34	0.42	195.51		15.00	69.83	68.00	4748.44	
B-36	55.7	25.60	25.60	25.15	25.00	0.60	33.42		15.00	8.36	79.00	660.44	
B-37	2.4	25.50	25.50	24.97	24.82	0.68	1.63		15.00	0.36	81.00	29.16	
B-38	13.7	25.47	25.47	25.28		0.19	2.60						現況：農道
B-39	25.6	25.20	25.20	24.86	24.72	0.48	12.29		14.00	3.58	88.00	315.04	
小計	15,723.6						5289.88	93.70		2432.94		90400.82	(2街区)
C-1	75.5	24.38	24.38	24.37	24.22	0.16	12.08		15.00	11.33	88.00	997.04	
C-2	176.0	24.61	24.61	24.07	23.92	0.69	121.44		15.00	26.40	81.00	2138.40	
C-3	99.7	24.34	24.34	24.19	24.04	0.30	29.91		15.00	14.96	80.00	1196.80	
C-4	121.9	24.42	24.42	24.25	24.10	0.32	39.01		15.00	18.29	77.00	1408.33	
C-5	66.0	24.54	24.54	24.35	24.20	0.34	22.44		15.00	9.90	69.00	683.10	
C-6	156.1	24.60	24.60	24.40	24.25	0.35	54.64		15.00	23.42	69.00	1615.98	
C-7	145.5	24.77	24.77	24.47	24.32	0.45	65.47		15.00	21.83	61.00	1331.63	
C-8	155.8	24.85	24.85	24.61	24.46	0.39	60.76		15.00	23.37	53.00	1238.61	
C-9	200.0	24.61	24.61	24.26	24.11	0.50	100.00		15.00	30.00	63.00	1890.00	
C-10	248.8	24.92	24.92	24.67	24.52	0.40	99.52		15.00	37.32	51.00	1903.32	
C-11	369.9	25.10	25.10	24.68	24.53	0.57	210.84		15.00	55.49	40.00	2219.60	
小計	1,815.2						816.11	0.00		272.31		16622.81	(緑地)

土量計算書

街区	面積 (m2)	計画高 (m)	路盤下高 (m)	現況高 (m)	表土剥ぎ後 地盤高(m)	高低差 (m)	盛土 (m3)	切土 (m3)	表土厚 (cm)	表土剥ぎ 土量(m3)	場内運搬 距離(m)	土量×距離	備考
E-1	3.4	26.59	25.24	25.90	25.74	-0.50		1.70	16.00	0.54	95.00	51.30	
E-2	319.4	26.69	25.34	26.26	26.06	-0.72		229.97	20.00	63.88	87.00	5557.56	
E-3	255.1	26.78	25.43	26.20	26.03	-0.60		153.06	17.00	43.37	56.00	2428.72	
E-4	23.9	26.84	25.49	26.03	25.85	-0.36		8.60	18.00	4.30	42.00	180.60	
E-5	181.7	26.94	25.59	26.37	26.24	-0.65		118.11	13.00	23.62	29.00	684.98	
E-6	155.1	27.05	25.70	26.43	26.30	-0.60		93.06	13.00	20.16	10.00	201.60	
E-7	41.3	27.12	25.77	26.63		-0.86		35.52					現況：農道
E-8	344.2	27.25	25.90	26.31	26.17	-0.27		92.93	14.00	48.19	1.00	48.19	
E-9	1.3	27.33	25.98	26.31	26.19	-0.21		0.27	12.00	0.16	6.00	0.96	
E-10	0.7	27.33	27.20	26.23	26.11	1.09	0.76		12.00	0.08	7.00	0.56	
E-11	91.6	26.58	26.45	26.26	26.06	0.39	35.72		20.00	18.32	93.00	1703.76	
E-12	86.1	26.67	26.54	26.20	26.03	0.51	43.91		17.00	14.64	59.00	863.76	
E-13	53.5	26.83	26.70	26.37	26.24	0.46	24.61		13.00	6.96	30.00	208.80	
E-14	44.6	26.94	26.81	26.43	26.30	0.51	22.75		13.00	5.80	11.00	63.80	
E-15	12.3	27.01	26.88	26.63		0.25		-3.08					現況：農道
E-16	50.5	27.14	27.01	26.31	26.17	0.84			14.00	7.07	6.00	42.42	
小計	1,664.7						127.75	730.14		257.09		12037.01	(1号道路)
1号道路	歩道計画高－R7造成高＝		0.13										
路床盛土	1,325.4					1.00	1325.40						
F-1	111.8	27.44	26.09	26.31	26.17	-0.08		8.94	14.00	15.65	1.00	15.65	
F-2	9.5	27.42	26.07	26.23	26.11	-0.04		0.38	12.00	1.14	4.00	4.56	
F-3	74.9	27.58	26.23	26.62	26.48	-0.25		18.73	14.00	10.49	2.00	20.98	
F-4	334.9	27.78	26.43	26.67	26.52	-0.09		30.14	15.00	50.24	1.00	50.24	
F-5	0.2	27.93	26.58	26.85	26.70	-0.12		0.02	15.00	0.03	4.00	0.12	
F-6	9.9	27.97	26.62	26.89	26.71	-0.09		0.89	18.00	1.78	3.00	5.34	
F-7	25.6	28.00	26.65	27.18		-0.53		13.57					現況：農道
F-8	229.1	28.13	26.78	27.13	26.98	-0.20		45.82	15.00	34.37	1.00	34.37	
F-9	19.7	27.44	27.31	26.31	26.19	1.12	22.06		12.00	2.36	7.00	16.52	
F-10	3.8	27.33	27.20	26.31	26.17	1.03	3.91		14.00	0.53	5.00	2.65	
F-11	34.7	27.33	27.20	26.23	26.11	1.09	37.82		12.00	4.16	6.00	24.96	
F-12	39.1	27.47	27.34	26.62	26.48	0.86	33.63		14.00	5.47	6.00	32.82	
F-13	71.0	27.67	27.54	26.67	26.52	1.02	72.42		15.00	10.65	6.00	63.90	
F-14	7.2	27.89	27.76	27.18		0.58	4.18						現況：農道
F-15	78.2	28.02	27.89	27.13	26.98	0.91	71.16		15.00	11.73	6.00	70.38	
小計	1,049.6						245.18	118.49		148.60		342.49	(2号道路)
2号道路	歩道計画高－R7造成高＝		0.13										
路床盛土	795.9					1.00	795.90						
G-1	43.0	26.44	26.19	26.43	26.30	-0.11		4.73	13.00	8.60	4.00	34.40	
G-2	23.5	26.44	26.19	26.60	26.46	-0.27		6.34	14.00	4.70	5.00	23.50	
G-3	4.6	26.44	26.19	26.64	26.47	-0.28		1.29	17.00	0.92	4.00	3.68	
G-4	80.0	26.44	26.19	26.85		-0.66		52.80					現況：農道
G-5	182.3	26.44	26.19	26.54	26.39	-0.20		36.46	15.00	36.46	7.00	255.22	
G-6	167.6	26.44	26.19	26.31	26.17	0.02	3.35		14.00	33.52	9.00	301.68	
小計	501.0						3.35	101.62		84.20		618.48	(1号調整池)
H-1	479.5	24.26	24.01	25.03	24.89	-0.88		421.96	14.00	95.90	72.00	6904.80	
H-2	15.1	24.26	24.01	25.37		-1.36		20.54					現況：農道
H-3	2.8	24.26	24.01	25.15	25.00	-0.99		2.77	15.00	0.56	79.00	44.24	
小計	497.4						0.00	445.27		96.46		6949.04	(2号調整池)
合計	30512.00						13618.17	1489.22		4708.67		196244.31	